

ESTIMATE

Schottenstein Roofing

1800 Northwest Blvd., Suite 210
Columbus, OH 43212
(614) 321-8888

Sales Representative

Dan 614-288-9192
dan@schottensteinroofing.com



2688 E. Broad Street
Columbus, OH 43209

Estimate #	1202
Date	10/11/23

Item	Description	Amount
Schottenstein Roofing System	<ul style="list-style-type: none"> - GAF Timberline HDZ Shingle 42.33 Squares Inc. waste - GAF Seal-A-Ridge Hip And Ridge Cap Shingles - GAF Pro Start Starter Shingles-Installed on Eaves And Rakes - Ice & Water Shield-Installed To Code (2 feet past warm wall) - Synthetic Deck Protection - Snow Country Ridge Vents - Aluminum Drip Edge - Material Delivery - Dumpster - Clean Up And Haul Away All Job Related Debris 	\$23,793.00
	Install 131 sheets of 4'x8' OSB	\$7,218.00

Sub Total	\$31,011.00
Total	\$31,011.00