

PROPOSAL- CITY OF BEXLEY, 2023 CURB & SIDEWALK IMPROVEMENTS

4a

TO: Mayor Ben Kessler

City of Bexley, Franklin County, Ohio

After a careful examination of the plans, Specifications, Form of Contract, and the site of the proposed work, the undersigned hereby proposes and agrees, if this proposal be accepted, to enter into Contract, using the form of Contract provided for, to furnish all equipment, labor, materials and construction to complete the said work in accordance with the terms and conditions specified, and to furnish a satisfactory bond, in the amount of One Hundred Percent of the total amount of the Contract, conditioned as and in the form prescribed by law as a guarantee for the faithful performance of the Contract, for the following prices:

BASE BID

"PRICE BID TO BE UNIT PRICE NOT LUMP SUM EXCEPT AS SHOWN"

Ref #	Item #	Description	Units	Quantity	Unit Prices in Figures			Total Extended Price
					Material	Labor	Total (Sum of Material & Labor)	
Spot Sidewalk Repair- Various Locations								
1	608	Remove and Replace Sidewalk, 4" thick, Class S, Spot Work Various Locations, Per BEX-ST-13	SF	8,500	3.94	14.90	18.84	160140.00
2	608	Remove and Replace Sidewalk, 6" thick, Class MS, Spot Work Various Locations, Per BEX-ST-13	SF	600	4.72	16.53	21.25	12750.00
3	202	Concrete Walk or Drive Approach Removed, S Drexel Avenue per plan or as directed	SF	2,400	0.00	5.18	5.18	12432.00
4	202	Concrete Curb or Curb and Gutter Removed, S Drexel Avenue per plan or as directed	LF	2,000	0.00	15.61	15.61	31220.00
5	203	Roadway Excavation including removal of pavement for Road Realignment, S Drexel Avenue per plan or as directed	CY	950	0.00	74.81	74.81	71069.50
6	608	Concrete Curb Ramp & Walk, S Drexel Avenue Per Plan or As Directed, Per BEX-ST-11	SF	3,000	2.89	5.94	8.83	26490.00
7	608	Detectable Warning Device, Wet Set, Armortile or approved equal, As Directed, Per BEX-ST-12.1	SF	300	27.50	52.26	79.76	23928.00
8	259	6" Concrete Drive Approach, Class MS, As Directed, Per BEX-ST-03	SF	700	4.14	7.61	11.75	8225.00
9	259	Remove and Replace 8" Concrete Alley Approach including Sidewalk, Class MS, As Directed, Per BEX-ST-01	SY	40	47.75	84.54	132.29	5291.60
10	605	6" Underdrain Pipe, As Directed (Bumpouts)	LF	1,050	4.68	22.43	27.11	28465.50
11	605	6" PVC Sch 40 Drain Pipe, As Directed (Bumpouts)	LF	950	11.75	55.82	67.57	64191.50
12	605	4" Underdrain Pipe, As Directed (Medians)	LF	1,650	3.87	17.88	21.75	35887.50
13	901	4" PVC Sch 40 with granular backfill and type 1 bedding per plan and as directed	LF	110	8.78	53.07	61.85	6803.50
14	915	4" Inserta Tee to connect to existing 12" or 15" Storm Sewer, per plan or as directed	Ea.	10	150.00	348.36	498.36	4983.60
15	Spec.	Reconnect Sump/ Downspout Drains (3" or 4" PVC), complete with new fernco couplings, As Directed, Per BEX-ST-20	LF	350	7.71	33.80	41.51	14528.50
16	Spec.	12"x12" ADS Storm Drain Box with Metal Grate, as directed for sump line connection to Storm Sewer	Ea.	35	500.00	808.72	1308.72	45805.20
17	609	Concrete Curb and Gutter, Class S, Per Plan or As Directed, Per BEX-ST-09, T=8", Complete Including Asphalt Pavement Repair	LF	400	29.76	23.81	53.57	21428.00
18	609	Concrete Curb Type VI (18"), Class S, Per Plan or As Directed, Including Asphalt Pavement Repair	LF	3,200	25.42	20.12	45.54	145728.00
19	253	Asphalt Pavement Replacement For Misc. Spot Repair, As Directed, Per BEX-UT-05	CY	120	165.00	654.46	819.46	98335.20
20	653	Topsoil Furnished and Placed for Road Realignment, As Directed	CY	1,100	40.00	40.00	80.00	88000.00
21	659	Seeding, Mulching & Fertilizer, road realignment areas S Drexel Ave, as directed	SY	1,300	1.00	2.50	3.50	4550.00

BASE BID

"PRICE BID TO BE UNIT PRICE NOT LUMP SUM EXCEPT AS SHOWN"

Ref #	Item #	Description	Units	Quantity	Unit Prices in Figures			Total Extended Price
					Material	Labor	Total (Sum of Material & Labor)	
Spot Sidewalk Repair- Various Locations								
22	604	Curb Inlet Reconstructed to Grade, As Directed	Ea.	10	500.00	1000.00	1500.00	15000.00
23	901	10" SDR 35 PVC Storm Sewer with Type 1 Bedding and Granular Backfill, As Directed	LF	10	10.00	101.67	111.67	1116.70
24	604	Precast Cub and Gutter Inlet, AA-S125, 36" depth, SE Corner of Bryden & S Drexel Ave, 10" outlet	Ea.	1	1800.00	6003.96	7803.96	7803.96
25	915	10" Inserta Tee to connect 10" PVC to existing 18" Storm Sewer, S Drexel Ave. per plan or as directed	Ea.	1	400.00	680.72	1080.72	1080.72
26	614	Maintenance of Traffic and Detours, S Drexel Avenue	LS	1	4000.00	90000.00	94000.00	94000.00
27	Spec.	Remove and Relay Brick Pavers, S Drexel Avenue at Drexel Circle for new curb installation	SF	40	5.46	33.57	39.03	1561.20
28	623	Construction Staking/ Layout Per Plan for S Drexel Ave	LS	1	1000.00	19000.00	20000.00	20000.00
29	Spec.	Force Account Contingency	LS	1	0.00	0.00	0.00	0.00

See Supplemental Specifications for each of the above items

 BIDDER'S TOTAL BASE BID \$ 1,050,815.18
ALTERNATE BID 1

"PRICE BID TO BE UNIT PRICE NOT LUMP SUM EXCEPT AS SHOWN"

Ref #	Item #	Description	Units	Quantity	Unit Prices in Figures			Total Extended Price
					Material	Labor	Total (Sum of Material & Labor)	
Sidewalk, Curb and Brick Strip Installation- S Drexel from Main to Sherwood, East Side								
1	202	Concrete Walk or Drive Approach Removed, S Drexel Avenue per plan or as directed	SF	2,300	0.00	5.40	5.40	12420.00
2	202	Concrete Curb or Curb and Gutter Removed, S Drexel Avenue per plan or as directed	LF	300	0.00	21.28	21.28	6384.00
3	605	Remove and Replace 6" Underdrain Pipe, As Directed	LF	300	4.68	25.32	30.00	9000.00
4	Spec.	Reconnect Sump/ Downspout Drains under walks or through curb (3" or 4" PVC), complete with new ferro concrete pipe, per BEX-ST-00	LF	30	7.71	33.80	41.51	1245.30
5	609	Concrete Curb Type VI (18"), Class S, Per Plan or As Directed, Including Asphalt Pavement Repair	LF	300	31.30	21.66	52.96	15888.00
6	608	Concrete Curb Ramp & Walk, S Drexel Avenue Per Plan or As Directed, Per BEX-ST-11	SF	2,300	3.93	5.07	9.00	20700.00
7	259	8" Concrete Drive Approach, Class MS, As Directed, Per BEX-ST-03	SF	140	7.03	8.55	15.58	2181.20
8	253	Asphalt Pavement Replacement For Misc. Spot Repair, As Directed, Per BEX-UT-05	CY	12	165.00	654.46	819.46	9833.52
9	Spec.	Install Brick Paver Strip per BEX-ST-18 on sand setting bed (Concrete Base for pavers to be included in item 608 Concrete Curb Ramp & Walk)	SF	480	8.00	11.80	19.80	9504.00
10	614	Maintenance of Traffic	LS	1	1300.00	3700.00	5000.00	5000.00

See Supplemental Specifications for each of the above items

 BIDDER'S TOTAL ALTERNATE BID 1 \$ 92,156.02

ALTERNATE BID 2

"PRICE BID TO BE UNIT PRICE NOT LUMP SUM EXCEPT AS SHOWN"

Ref #	Item #	Description	Units	Quantity	Unit Prices in Figures			Total Extended Price
					Material	Labor	Total (Sum of Material & Labor)	
Sidewalk, Curb and Drive Replacement- Columbia Place								
1	202	Concrete Walk or Drive Approach Removed as directed	SF	2,250	0.00	4.15	4.15	9337.50
2	202	Concrete Curb or Curb and Gutter Removed as directed	LF	80	0.00	18.63	18.63	1490.40
3	203	Roadway Excavation including removal of pavement for Road Realignment, S Drexel Avenue per plan or as directed	CY	12	0.00	74.81	74.81	897.72
3	605	Remove and Replace 6" Underdrain Pipe, As Directed	LF	80	3.50	26.50	30.00	2400.00
4	Spec.	Reconnect Sump/ Downspout Drains to existing 10" storm drain as shown on plan (4" PVC), complete with new 10"x4" wye and fernco couplings, As Directed	Ea	3	300.00	1821.32	2121.32	6363.96
5	609	Remove and Replace Existing Mountable Concrete Curb & Gutter Spot Work, Class S, as Directed, Including Asphalt Pavement Repair	LF	300	26.57	41.59	68.16	20448.00
6	608	Concrete Walk 6" thick, Spot Work As Directed, Per BEX-ST-06 & BEX-ST-11	SF	2,300	4.77	5.28	10.05	23115.00
7	259	6" Concrete Drive Approach, Class MS, As Directed, Per BEX-ST-03	SF	700	5.01	6.74	11.75	8225.00
8	253	Asphalt Pavement Replacement For Misc. Spot Repair, As Directed, Per BEX-UT-05	CY	5	165.00	654.46	819.46	4097.30
9	Spec.	Remove and Reinstall Existing Brick Paver Strips to match Existing Driveways (Concrete Base for pavers to be included in item 259 Concrete Drive Approach)	SF	80	6.00	21.50	27.50	2200.00
10		Remove and Replace Reinforced Concrete Storm Inlet Top Slab at 480 Columbia Place	Ea	1	500.00	1000.00	1500.00	1500.00
11		Adjust Sanitary Sewer MH to match new sidewalk at 505 Columbia Place	Ea.	1	500.00	500.00	1000.00	1000.00
12		Relocate Existing Surface Inlet in Roadway in front of 510 Columbia Place to allow for curb replacement, as directed	Ea	1	170.00	2171.44	2341.44	2341.44
13		Remove Existing Fire Hydrant at 480 Columbia Place and Install new Fire Hydrant (provided by City) at 510 complete with new 8x6 cut in tee, 6" gate valve and 6" DI CI 53 pipe	LS	1	4020.00	11371.92	15391.92	15391.92

See Supplemental Specifications for each of the above items

BIDDER'S TOTAL ALTERNATE BID 2 \$ 98,808.24

2023 BEXLEY CURB & SIDEWALK IMPROVEMENTS

BID SUMMARY:

BIDDER'S TOTAL BASE BID \$ 1,050,815.18

BIDDER'S TOTAL ALTERNATE BID 1 \$ 92,156.02

BIDDER'S TOTAL ALTERNATE BID 2 \$ 98,808.24

THE ESTIMATED QUANTITIES ARE APPROXIMATE BEING GIVEN ONLY AS A UNIFORM BASIS FOR THE COMPARISON OF BIDS, AND THE CITY RESERVES THE RIGHT TO INCREASE, DECREASE OR OMIT THE AMOUNT OF ANY CLASS OR PORTION OF THE WORK DURING THE PROGRESS OF CONSTRUCTION WITHOUT CHANGES TO THE UNIT PRICE BID.

NAME OF FIRM Decker Construction Company DATE February 22, 2023

SIGNATURE:  TITLE President

ADDRESS: 3042 McKinley Avenue Columbus, Ohio 43204

PHONE NO.: (614) 488-7958

ADDENDUM (S) RECEIVED (SIGN WHEN APPLICABLE)

1) _____ 2) _____ 3) _____

Note: Bidder is responsible for accuracy and verification of all spreadsheet calculations and numbers