1 PLANTING PLAN ENLARGEMENT - WEST
SCALE: 1"=10'-0"

PLANTING SCHEDULE

SYM	QTY	LATIN NAME	COMMON NAME	SIZE	SPACING/NOTES
EVERGREEN TREES					
IOA	1	Ilex opaca	American Holly	12-14	As shown | 6' Skirt
IOB	4	Ilex opaca	American Holly	14-16	As shown | 8' Skirt
PAA	1	Picea abies	Norway Spruce	12-14	As shown | 8' Skirt
PAB	7	Picea abies	Norway Spruce	16-18	As shown | 10' Skirt
TGA	2	Thuja plicata 'Green Giant'	Green Giant Arborvitae	12-14	As Shown | 6' Skirt
TGB	16	Thuja plicata 'Green Giant'	Green Giant Arborvitae	14-16	As shown | 8' Skirt
TV	3	Thuja plicata 'Growspit'	Spring Grove Arborvitae	12-14	As Shown | 6' Skirt
TS	23	Thuja occidentalis 'Smaragd'	Smaragd Arborvitae	12-14	As Shown | 4' Skirt
ORNAMENTAL TREES					
SYM	QTY	LATIN NAME	COMMON NAME	SIZE	SPACING/NOTES
CF	1	Cornus florida	White Flowering Dogwood	4" cal.	Single Stem | Specimen
MV	2	Magnolia virginiana 'Jim Wilson'	Sweet Bay Magnolia	14-16'	As Shown | Multi-stem
SHRUBS					
SYM	QTY	LATIN NAME	COMMON NAME	SIZE	SPACING/NOTES
AZ	72	Azalea x girard 'Pleasant White'	Pleasant White Azalea	#5	24-30" | 30" o.c.
BA	110	Buxus sempervirens	Boxwood	48"	Globe
BB	3	Buxus sempervirens	Boxwood	36"	Globe
BC	4	Buxus sempervirens	Boxwood	24"	Globe
FG	24	Fothergilla 'Mt. Airy'	Mt. Airy Fothergilla	4'	Heavy | As Shown
HQ	10	Hydrangea quercifolia 'Snow Queen'	Snow Queen Oakleaf Hydrangea	4.5'	As Shown
RM	23	Rhododendron maximum	Rosebay Rhododendron	4-5'	Heavy | As Shown
VC	2	Viburnum carlesii	Korean spice viburnum	4'h	Heavy | As Shown
HEDGING					
SYM	QTY	LATIN NAME	COMMON NAME	SIZE	SPACING/NOTES
BNF	109	Buxus 'NewGen Freedom'	NewGen Freedom Boxwood	24-30" ht.	15" o.c. | Hedge Quality
CAA	6	Carpinus betulus	Hornbeam	4-5'	20" o.c. | Hedge Quality
CAB	44	Carpinus betulus	Hornbeam	6-7'	20" o.c. | Hedge Quality
TMA	16	Taxus x media 'Hicksii'	Yew	36-42"	30" o.c. | Hedge Quality
TMB	10	Taxus x media 'Hicksii'	Yew	6-7' ht.	30" o.c. | Hedge Quality

PLANTING NOTES

1. PRIOR TO ANY PLANTING OR PLACEMENT OF TOPSOILS OR SUBSOILS, SUBSOIL SHALL BE SCARIFIED. DEPTH TO BE DETERMINED IN THE FIELD AND BASED ON EXISTING CONDITIONS AND CONDITIONS RESULTING FROM CONSTRUCTION TRAFFIC AND ACTIVITIES. LANDSCAPE CONTRACTOR TO INSPECT SUBSOILS IN ORDER TO VERIFY THAT THEY ARE NOT OVERLY COMPACTED, ARE WELL-DRAINING, AND WILL NOT NEGATIVELY IMPACT THE GROWTH AND HEALTH OF PLANT MATERIALS. LANDSCAPE CONTRACTOR SHALL REPORT ANY DEFICIENCIES IN SUBSOILS IN WRITING TO THE LANDSCAPE DESIGNER AND GENERAL CONTRACTOR.
2. NO RUBBER-TIRED EQUIPMENT OR HEAVY EQUIPMENT EXCEPT SMALL BULLDOZER SHALL PASS OVER SOILS AFTER THEY HAVE BEEN LOOSENED OR PLANTING MEDIUM IS SPREAD TO PREVENT COMPACTION.
3. ALL STRUCTURAL IMPROVEMENTS AND INSTALLATIONS TO BE DONE PRIOR TO PLANTING.
4. ALL PLANT MATERIAL TO CONFORM WITH THE LATEST EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK OF THE AMERICAN ASSOCIATION OF NURSERYMEN. ALL TREES TO BE NURSERY-GROWN, HEALTHY AND TRUE TO TYPE SPECIFIED.
5. CONTRACTOR RESPONSIBLE FOR VERIFYING PLANTING MATERIALS AND QUANTITY. CONTRACTOR SHALL LAY OUT ALL PLANTING MATERIAL IN FIELD FOR REVIEW AND APPROVAL BY LANDSCAPE DESIGNER PRIOR TO PLANTING.
6. CONTRACTOR RESPONSIBLE FOR VERIFYING SEED MATERIAL WITH LANDSCAPE DESIGNER PRIOR TO ORDERING.
7. LANDSCAPE DESIGNER RESERVES THE RIGHT TO REQUEST PHOTOS OF PLANT MATERIAL FOR APPROVAL PRIOR TO ORDERS BEING PLACED BY THE CONTRACTOR.

0 10' 20'
SCALE: 1"=10'

NORTH

1. Survey provided by Landmark Survey Group, Inc.

2. Kathryn Herman Design, LLC takes no responsibility for the accuracy of the information provided by the survey. If the Contractor determines inaccuracies on site, the Contractor shall alert the Landscape Designer prior to construction of any part of the design affected by the perceived inaccuracy.

3. The Contractor shall verify the location of all utilities prior to commencement of any construction activities. The Contractor takes full responsibility for any utilities damaged due to not verifying utility locations, and will repair any damage at the Contractors own expense.

4. The Contractor shall obtain all permits for construction activities as required by the local municipality, state and federal regulations. All permits shall be obtained prior to commencement of the work associated with the permit. The Contractor shall abide by all rules and regulations set forth by the permits required for construction activities.

5. The Contractor shall at all times keep the construction site in an orderly condition, store materials in a pre-determined location, minimize site disturbances, and remove all debris and excess material from the site.

6. The Contractor shall maintain any erosion control measures utilized on site.

7. In the event that Kathryn Herman Design, LLC is not engaged in construction administration and the direct supervision of project installation, nor shall it be liable for any damages resulting from attempts by other parties to execute the plans and details included in this document.

NO.	DATE	SHEET & DESCRIPTION	BY

FILE: L1.P-T.02 TREES & SHRUBS ENLARGEMENT - WEST.DWG
DRAWN BY: H.L, M.L.
CHECKED BY: KH
SAVE DATE: 2024-9-3
ISSUE DATE: 2024-09-03

K H | D
KATHRYN HERMAN DESIGN
215 ELM STREET
NEW CANAAN, CT 06840
P 203 966 1221

PROJECT:
HUNTINGTON HOUSE
81 NORTH DREXEL AVENUE
BEXLEY, OHIO

DWG. TITLE:
TREES & SHRUBS ENLARGEMENT - WEST

NOT FOR CONSTRUCTION
TREE & PUBLIC GRADEN COMMISSION SUBMITTAL

SHEET NO.
L-7.01

© KATHRYN HERMAN DESIGN, LLC