



Bexley City Hall Office Renovation

Addendum # 2

May 12, 2025

Question: Will this project require off-hours? If so, then what are the hours of operation to work around?

Answer: The only anticipated off-hours work will be when the Server is relocated and electrical work associated with the server is being performed. This will need to be weekend work. Other than that, standard working hours are acceptable.

Question: The door schedule on G00 calls for new wood veneer doors to match existing at the new server room (D117) and supply closet (D118), but new door hardware is not identified. What hardware should be included for each of these doors? Please confirm that these should receive new hollow metal frames.

Answer: See attached Door Hardware schedule from the 2014 Build out of the building. This was taken out of the approved as noted door hardware submittal from the door supplier. This is what we would like to be matched.

Hardware Schedule

Project ID: 140711BSCHR - Bexley Square City Hall Renov.

Heading #: 3

		1 SGL Door:106B	Office 106 to Restroom 106A	LH	
		3' 0" x 8' 0" x 1 3/4" WDD/HMF			DE
4 EA	Hinge	5BB1HW 4.5" x 4.5" NRP	652	(HI-1) Ives	
1 EA	Mortise Lock	L9496 T L583-363 03C 09-664 10-072-1-3/16"	626	(LO-1) Schlage	
1 EA	Cylinder	23-030	626	(CY-3) Schlage	
1 EA	Kick Plate	8400 B4E 10" x 34"	US32D	(KP-1) Ives	
1 EA	Wall Stop	WS407CCV	630	(ST-1) Ives	
4 EA	Silencer	SR64-GRY		(SI-1) Ives	
1 EA	Coat Hook	582	626	(OT-1) Ives	

Heading #: 4

		1 SGL Door:101B	Corridor from Council Chambers 101	LHR	
		3' 0" x 8' 0" x 1 3/4" WDD/HMF			DE✓
4 EA	Hinge	5BB1HW 4.5" x 4.5" NRP	652	(HI-1) Ives	
1 EA	Rim Exit Device	CI 99L 996L x03	US26D	(ED-3) Von Duprin	
1 EA	Housing	20-059	626	(CY-1) Schlage	
1 EA	Cylinder	20-079	626	(CY-2) Schlage	
2 EA	Cylinder	23-030	626	(CY-3) Schlage	
2 EA	Construction Core	23-030-ICX 50-231		(CY-4) Schlage	
1 EA	Surface Closer	4111 MC MTLPC EDA TBSRT	AL	(CL-7) LCN Closers	
1 EA	Wall Stop	WS407CCV	630	(ST-1) Ives	
4 EA	Silencer	SR64-GRY		(SI-1) Ives	
1 EA	Keying	Master Keying Charge		(OT-3) Ott Incorporated	

Heading #: 5

		1 SGL Door:102A	Filing Area to Employee Lounge 102	LH	
		3' 0" x 8' 0" x 1 3/4" WDD/HMF			DE✓
4 EA	Hinge	5BB1HW 4.5" x 4.5"	652	(HI-2) Ives	
1 EA	Push Plate	8200-4x16	630	(PP-3) Ives	
1 EA	Pull Plate	8302-8-4x16	630	(PP-4) Ives	
1 EA	Surface Closer	4011T MC MTLPC BUMPER TBSRT	AL	(CL-6) LCN Closers	
1 EA	Kick Plate	8400 B4E 10" x 34"	US32D	(KP-1) Ives	
4 EA	Silencer	SR64-GRY		(SI-1) Ives	

Heading #: 6

		1 SGL Door:102AA	Employee Lounge 102 to Mech Room 102A	LH	
		3' 0" x 8' 0" x 1 3/4" WDD/HMF			DE✓
4 EA	Hinge	5BB1HW 5" x 4.5"	652	(HI-3) Ives	
1 EA	Cylindrical Lock	ND94 T D TLR 13-047 10-025-1-3/16"	626	(LO-2) Schlage	
1 EA	Cylinder	23-030	626	(CY-3) Schlage	
1 EA	Kick Plate	8400 B4E 10" x 34"	US32D	(KP-1) Ives	
4 EA	Silencer	SR64-GRY		(SI-1) Ives	
1 EA	Keying	Master Keying Charge		(OT-3) Ott Incorporated	

Heading #: 6.1

3'-0"x8'-0"x1 3/4"

		1 SGL Door:113A	Filing Area to Chair Storage	RHR	
		3' 0" x 7' 0" x 1 3/4" WDD/HMF			
4 EA	Hinge	5BB1HW 5" x 4.5"	652	(HI-3) Ives	
1 EA	Cylindrical Lock	ND94 T D TLR 13-047 10-025-1-3/16"	626	(LO-2) Schlage	
1 EA	Cylinder	23-030	626	(CY-3) Schlage	
1 EA	Kick Plate	8400 B4E 10" x 34"	US32D	(KP-1) Ives	
4 EA	Silencer	SR64-GRY		(SI-1) Ives	
1 EA	Keying	Master Keying Charge		(OT-3) Ott Incorporated	

Material Schedule

Project ID: 140711BSCHR
Job Number:

Bexley Square City Hall Renov.

Openings DE✓						Frames										Doors								Special Instructions			
Door #	Size	Location	Label	Hand	Thickness	Material	Qty	Jamb Depth	Profile	Ga	S.T.	Const	Anchor	Elevation	Elev. Sheet	Anchor Sheet	Material	Qty	Group	Specie	Elevation	Elev. Sheet	Exterior	Undercut	Astragal	Hdw Set #	
100B	3' 0" x 8' 0"	Filing Area from Corridor		LHR	1 3/4"	HMF	1	5 3/4"	F	16	CR	SMT	MP	SL2L R	6	4	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	13
100C	3' 0" x 8' 0"	Corridor to Workstop Production Storage		LH	1 3/4"	HMF	1	5 3/4"	F	16	CR	SMT	MP	SL2L	5	4	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	13.1
101B	3' 0" x 8' 0"	Corridor from Council Chambers 101		LHR	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	4
102A	3' 0" x 8' 0"	Filing Area to Employee Lounge 102		LH	1 3/4"	HMF	1	5 3/4"	F	16	CR	SMT	MP	SL2L	5	4	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	5
102AA	3' 0" x 8' 0"	Employee Lounge 102 to Mech Room 102A		LH	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	6
103AA	3' 0" x 8' 0"	Filing Area to Employee Restroom 103A		RH	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	7
104A	3' 0" x 8' 0"	Corridor to Mens 104		RH	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	8
105A	3' 0" x 8' 0"	Corridor to Womens 105		LH	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	8
106B	3' 0" x 8' 0"	Office 106 to Restroom 106A		LH	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	3
109B	6' 0" x 8' 0"	Galley 109 Closet		Bypass	1 3/4"	HMF	1	5 7/8"	CO	16	CR	KD	CA	CO	4	4A	WDD	1		PSWH OAK	WF	7				Bi-pass pair 3 1/4" Undercut. No other undersizing.	14
																	WDD	1		PSWH OAK	WF	7				3 1/4" Undercut	
109C	6' 0" x 8' 0"	Galley 109 Closet		Bypass	1 3/4"	HMF	1	5 7/8"	CO	16	CR	KD	CA	CO	4	4A	WDD	1		PSWH OAK	WF	7				Bi-pass pair 3 1/4" Undercut. No other undersizing.	14
																	WDD	1		PSWH OAK	WF	7				3 1/4" Undercut	
112A	3' 0" x 8' 0"	Lobby 100 from Multi-Use 112		LHR	1 3/4"	HMF	1	5 3/4"	F	16	CR	SMT	MP	SL2L R	6	4	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	11
113A	3' 0" x 7' 0" 8' 0"	Filing Area to Chair Storage		RHR	1 3/4"	HMF	1	5 7/8"	DW	16	CR	KD	CA	S	4	4A	WDD	1		PSWH OAK	WF	7		X		Undercut 3/4"	6.1

8'-0

AC